Register 30001	Circuit 1	Total cable length in meter
Register 30002	Circuit 1	Total cable length in feet
Register 30003	Circuit 1	Status leak detection cable
		(0=Normal, 1 = Service, 2 = Leak, 3 = Cable fault)
Register 30004	Circuit 1	Leak location in meter
Register 30005	Circuit 1	Leak Zone
Register 30006	Circuit 1	Leakvalue in %
Register 30007	Circuit 2	Total cable length in meter
Register 30008	Circuit 2	Total cable length in feet
Register 30009	Circuit 2	Status leak detection cable
		(0=Normal, 1 = Service, 2 = Leak, 3 = Cable fault)
Register 30010	Circuit 2	Leak location in meter
Register 30011	Circuit 2	Leak Zone
Register 30012	Circuit 2	Leakvalue in %
Register 30013	Circuit 3	Total cable length in meter
Register 30014	Circuit 3	Total cable length in feet
Register 30015	Circuit 3	Status leak detection cable
		(0=Normal, 1 = Service, 2 = Leak, 3 = Cable fault)
Register 30016	Circuit 3	Leak location in meter
Register 30017	Circuit 3	Leak Zone
Register 30018	Circuit 3	Leakvalue in %
Register 30019	Circuit 4	Total cable length in meter
Register 30020	Circuit 4	Total cable length in feet
Register 30021	Circuit 4	Status leak detection cable
		(0=Normal, 1 = Service, 2 = Leak, 3 = Cable fault)
Register 30022	Circuit 4	Leak location in meter
Register 30023	Circuit 4	Leak Zone
Register 30024	Circuit 4	Leakvalue in %

Register 30025	Temperature value	temperature*10
Register 30026	Temperature status	0 = normal 1 = low 2 = high
Register 30027	Humidity value	humidity*10
Register 30028	Humidity status	0 = normal 1 = low 2 = high